BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK INDENT50413

Name of Work: Providing chambers to existing borewell and conscaling to road surface area inn ward No.13 Shettihalli sub-division.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri NAVEEN R (RNI ENTERPRISES)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	100.36	468.32	Rupees Four Hundred Sixty Eight and Thirty Two Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	5.74	5321.6	Rupees Five Thousand Three Hundred Twenty One and Sixty Paise Only

Signature of the Contractor,

Executive Engine
Dasarahalli Divisi

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palik
Dasarahalli Division, Bengaluru-73

3	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	30.52	6062.1	Rupees Six Thousand Sixty Two and Ten Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 550 with all lead and lift charges & as per direction of engineer incharge of work.	Cum	2.14	91755.0	Rupees Ninety One Thousand Seven Hundred Fifty Five Only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. with all lead and lift charges & as per direction of engineer incharge of work.	Cum	165.24	373.41	Rupees Three Hundred Seventy Three and Forty One Paise Only

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Signature of the Contractor,

Executive Engineer,

6	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 50mm nominal OD pipeswith all lead and lift charges & as per direction of engineer incharge of work.	Cum	238.00	485.01	Rupees Four Hundred Eighty Five and One Paise Only
7	Providing and laying 25cm thick Pre Cast Cover slabs including cost of all materials, labours, curing, transportation, loding unloding etc.., complete as per the direction of Engineer in charge. with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	38.25	5331.3	Rupees Five Thousand Three Hundred Thirty One and Thirty Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Executive Engineer
Dasarahalli Division